

Lakeland Boat and RV
 County Owned Utilities
OPINION OF PROBABLE COST
 5/12/2024

DESCRIPTION	ESTIMATED TOTAL QUANTITY	UNIT	UNIT PRICE	ESTIMATED TOTAL AMOUNT
Curb, Striping, and Paving				
10" PVC, AWWA C-900, DR 18, Blue	20	LF	\$ 66.90	1,338.00
10" DIP, Pressure Class 350, Cement-Lined, Bituminous Coated	9	LF	\$ 66.90	602.10
10" Gate Valve Assembly, Complete	2	EA	\$ 3,262.00	6,524.00
10" 45 Degree Bend, DI, C153, Cement-Lined, Bituminous Coated	1	EA	\$ 707.00	707.00
10" 90 Degree Bend, DI, C153, Cement-Lined, Bituminous Coated	3	EA	\$ 707.00	2,121.00
10" Tee, DI, C153, Cement-Lined, Bituminous Coated	1	EA	\$ 707.00	707.00
10"x2" Tapped Plug MJ	1	EA	\$ 707.00	707.00
10" HDPE	240	LF	\$ 148.68	35,683.20
12"x10" TSV	1	EA	\$ 11,620.00	11,620.00
ESTIMATED TOTAL COST				\$ 60,009.30
10% BOND AMOUNT			10% of Total	\$ 6,000.93
<i>Kimley-Horn does not control the cost of labor, materials, equipment of services furnished by others, methods of determining prices, or competitive bidding or market conditions, any opinions rendered as to costs, including but not limited to opinions as to the costs of construction and materials, shall be made on the basis of its experience and represent its judgement as an experienced and qualified professional, familiar with the industry. Kimley-Horn cannot and does not guarantee that proposals, bids or actual costs will not vary from its opinions of cost.</i>				



Jon P. Scott
 This item has been electronically
 signed and sealed by Jon Patrick
 Scott P.E. on the time and date stamp
 shown using this digital signature.
 Printed copies of this document are
 not considered signed and sealed, the
 signature must be verified on any
 electronic copies.
 2024.06.03 13:25:37 -04'00'



330 West Church Street
PO Box 9005 • Drawer GM03
Bartow, Florida 33831-9005

PHONE: 863-534-6792
FAX: 863-534-6407
www.polk-county.net

LAND DEVELOPMENT DIVISION

MEMORANDUM

To: Rebecca Spangler, Project Coordinator

From: Martin Waring, Inspector

Project Name: Lakeland Boat & RV Storage

Project #: LDNON-2022-109 PCUMD Project # 2022-11-30-0

DATE: May 24, 2024

The Inspector of Record has made a final review of the above-mentioned project. As a result of inspections, test results, and general site observations, I certify that the project is complete and represents reasonable compliance with the intent of the plans designed by the Engineer of Record and approved by the Polk County Land Development Division. The exact field locations and elevations of the storm water, potable water, wastewater, and reclaimed water systems are not guaranteed nor certified by the inspector.

It is the Contractor and Engineer of Record's responsibility to furnish the Polk County Land Development Division with Record Drawings and other final closeout documentation, as required by the Land Development Code and the Utility Standards and Specifications Manual, for final review and approval of the completed project before release of C.O.'s.

Should you have any further questions in the matter, please call (863) 534-6449.